

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>31W</u>	<u>C2</u>
	T <u>49N</u> R <u>31W</u>	<u>A2</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Jun 19 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C2) Quarter corner common to Sections 5 and 6. 1975 - Remonumented in the original position by K.L.Sackett RLS from original BT Maple 10" N15W 18 links, then found 21" DBH. Set 1"IDx36" I.pipe with 4" aluminum cap. 8" Cedar N82E 15.4', 10" Sugar S41W 21.1'.
 (A2) Quarter corner common to Section 6 T49N-R31W and Section 1 T49N-R32W. 1975 - K.L.Sackett RLS remonumented the corner at the position of a 1.5" ID iron pipe, found in the original position, at record bearing and distance from original bearing tree Maple 8" N79E 22 links. Set 1"IDx36" I.pipe with 4" aluminum cap. 6" Sugar North 16.9', 12" Sugar N79W 20.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C2) Recovered the 1975 monument in good condition and at record bearing and distance from the 1975 witnesses. The Cedar is in good condition, the Sugar is a standing dead stub. The original BT Maple noted in the 1975 record is a decaying stump, at record bearing and distance. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.
 (A2) The 1975 monument was not recovered and appears to have been removed by heavy equipment, which seems to have also destroyed the original BT Maple, not recovered. Reestablished the position for the corner at record bearing and distance from the 1975 NBTs. The NBT Sugar N79W is now a dead standing stub with scribing visible. The NBT Sugar North is in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C2) Fd. 1"ID I.pipe with 4" alum. State of Michigan cap. Set measuring nails in:	(A2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
12" Cedar N88E 16.0' scribing vis. *	12" Sugar N07E 17.1' old marks vis. *
8" Sugar S12E 20.85' mrkd "1/4S NBT"	5" Sugar N69E 26.6' mrkd "1/4S NBT"
19" Y.Birch N74W 7.65' do	6" Sugar S56E 15.65' do
14" Maple N57E 13.70' do	4" Sugar N80W 19.6' do
Sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1975 NBT.	Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1975 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/18/07