

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Baraga  
(County)

	Located In:	Corner Code #/
1 Public Land Survey	T 49N R 62W	D11
	T R	D12
	T R	F11
	T R	
2 Property Controlling in Section	S32 T R	2
	S T R	
3 Miscellaneous Property in Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4 Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

I, Keith Sackitt, in a field survey on October 15, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	20	29	28	27	26	25							
11													
12	31	30	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

D11	B12	F11	2
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D11	B12	F11	2
Restored midway on line.	Established during section subdivision.	Restored midway on line.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D11	B12	F11	2
Set 1"x1.0"x32" I.P. w/4" aluminum cap.	Set 1"x36" I.P. w/4" aluminum cap.	Set 1"x36" I.P. w/4" aluminum cap.	Set 1"x1.0"x36" I.P. w/4" aluminum cap.
3" balsam N51W 43.1' 1/4s NBT	10" sugar S36E27.2' 1/4s NBT	16" sugar 36.9' S70W 1/4s NBT	5" sugar S31W 4.6' 1/16s BT
Bearing rock N63W 37.5' painted	16" cedar N15W 7.8' 1/4s NBT	3" cedar 32.2' S05E 1/4s NBT	10" sugar S50E 2.3' 1/16s BT
6" hallowlock S24W 46.6' 1/4s NBT	12" balsam S55E 17.1' 1/4s NBT	5" maple 41.2' N15E 1/4s NBT	8" sugar N65W 13.2' 1/16s BT
			3" sugar N41E 3.0' SQUARED

Signed by Keith Sackitt Date 12-9-88

Surveyor's Michigan License No. 19006