

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga

----- (County)	Located In:	Corner Code ##
1. Public Land Survey	T 49N R 32W	E12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 32 T R	1
	S T R	7
3. Miscellaneous Property in Sec.	S T R	14
	S T R	

Register of Deeds Stamp & File Number

4 Lot No. _____, Recorded Plat _____
5 Private Claims _____

I, Keith Backett, in a field survey on September 27, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5											
3													
4	7	8	9		10	11							
5													
6	12	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E12	1	7	14
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E12	1	7	14
Restored midway on line.	Established midway on line.	Established midway on line.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E12	1	7	14
Set 1"x36" I.P. w/4" aluminum cap.	Set 1" I.D. by 32" I.P. w/4" aluminum cap.	Set 1"x 36" I.P. w/4" aluminum cap.	Set 1" x 36" I.P. w/4" aluminum cap.
10" sugar N10W 34.2' 1/4S NBT	8" maple S35W 15.0' 1/16S BT	16" cedar S38W 37.4' 1/16S BT	10" sugar N74W 11.5' 1/16S BT
14" hemlock S68E 7.8' 1/4S NBT	4" y.birch S64E 11.8' 1/16S BT	10" cedar N76E 20.6' 1/16S BT	12" sugar S18W 6.5' 1/16S BT
7" cedar S14W 41.0' 1/4S NBT	6" cedar N13W 39.4' 1/16S BT	5" maple N42W 22.8' 1/16 S BT	6" sugar N03W 6.9' 1/16S BT

Signed by

Keith Backett

Date

12-22-88

Surveyor's Michigan License No.

19006