

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 T Baraga

County	Located In:	Corner Code =#
1 Public Land Survey	T 49N R 32W	A10
	T R	A11
	T R	
	T R	
2 Property Controlling in Section	S 30 T R	3
	S T R	10
3 Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4 Lot No _____, Recorded Plat _____
 5 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith Sackett, in a field survey on July 11, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

A10	A11	3	10
Original monument and accessories not found.	Original monument and accessories not found. Found old square cedar post used as corner for many years.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A10	A11	3	10
Restored midway and on line.	Restored at old cedar post.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A10	A11	3	10
Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 36" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.
5" sugar N72E 20.2' 1/4s NBT	24" cedar S33W 9.0' S36 NBT	24" cedar S86E 31.0' 1/16s BT	16" sugar N08E 6.5' 1/16s BT
6" sugar N20W 26.8' 1/4s NBT	24" spruce N52E 28.9' S30 NBT	4" sugar N22W 8.2' 1/16s BT	12" yellow birch S26W 3.2' 1/16s BT
12" sugar S42E 12.6' 1/4s NBT	4" maple N41W 29.8' S25 NBT	7" sugar S52W 6.5' 1/16s BT	5" sugar S71E 14.1' 1/16s BT

Signed by Keith Sackett Date August 27, 1990

Surveyor's Michigan License No. 19006