

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 49 ^{N.} _{S.} , R. 32 ^{K.} _{W.}	A7, A8, A9
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, ^{N.} _{S.} , R. _____, ^{E.} _{W.}	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, ^{N.} _{S.} , R. _____, ^{E.} _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 24, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner A-7: Original monument and accessories not found. Found pipe and scribed tree by R.L.S. Norman Thompson - not recorded at court house.
- Corner A-8: Original monument and accessories not found.
- Corner A-9: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner A-7: Re-established at pipe.
- Corner A-8: Re-established on line between section corners.
- Corner A-9: Re-established by land calls and other corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner A-7: Set 1 1/4" I.D. x unknown length iron pipe.
 - 9" Cedar N07°E 34.9' S18, NBT
 - 13" Sugar S20°W 19.7' S24, NBT
 - 5" Sugar S25°E 19.4' S19, NBT
 - 16" Y.Birch N81°W 22.3' - previously scribed by N. Thompson
- Corner A-8: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 - 4" Cedar S81°E 7.5' 1/4S, NBT
 - 6" Cedar N16°E 18.1' 1/4S, NBT
 - 8" Cedar S22°W 44.5' 1/4S, NBT
- Corner A-9: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 - 16" W. Pine N89°W 12.6' S24, NBT
 - 6" Cedar S56°E 47.5' S30, NBT
 - 5" Spruce S20°W 20.0' S25, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

DATE 11/23/80

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

