

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

RECEIVED

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. S., R. <u>32</u> X. W.	<u>C-11, B-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

SEP 29 1976

LANDS DIVISION

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 22, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner B-11: Original monument and accessories not found. Old blazed lines east & west.
 - Corner C-11: Original monument and accessories not found. Old blazed lines north, south, east and west.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner B-11: This corner reestablished on line between section corners at old post location.
 - Corner C-11: This corner reestablished by double proportionate measurement between land calls north, south east and west.


- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner B-11: Set 1" I.D. x 36" iron pipe with a 4" aluminum cap.
 - 8" Sugar N50°E 14.6' 1/2S, NBT
 - 6" Sugar N63°W 27.6' 1/2S, NBT
 - 4" Sugar S16°E 16.9' 1/2S, NBT
 - Corner C-11: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 - 7" Sugar S84°W 3.5' S31, NBT
 - 7" Sugar S48°E 5.8' S32, NBT
 - 12" Sugar N48°E 6.6' S29, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Keith L. Sackett DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY Keith L. Sackett DATE September 27, 1976
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006