

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	BARAGA COUNTY LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 49 N. 32 R. 32 W.	G4, G5, E3, F3
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 21, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G4: Original monument and accessories not found.
 - Corner G5: Original monument and accessories not found. Found old blazed line and paint line intersection. This fits good by double proportion distance.
 - Corner E3: Original monument and accessories not found. Found old fence line south.
 - Corner F3: Original monument and accessories not found. Found old N-S-E-W blazes, old location posters and an old post.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G4: Restored on line and midway between corners north and south.
 - Corner G5: Restored at old blazed line intersection.
 - Corner E3: Restored in center line. Old road in line with fence south. This position checks well with other corners in area. Old blazed line north.
 - Corner F3: Restored at old post. This position checks nearly midway and on line between corners east and west.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|---|---|
| Corner G4: Set 1" I.D.x32" iron pipe with 4" alum. cap.
14" Cedar N81W 43.9 ft. 1/4S,NBT
10" Spruce S06W 15.7 ft. 1/4S,NBT
4" Spruce S73E 12.1 ft. 1/4S,NBT | Corner G5: Set 1" I.D.x32" iron pipe with 4" alum. cap.
7" Sugar S01W 10.5 ft. S16,NBT
10" Sugar N65E 18.3 ft. S10,NBT
12" Sugar N57W 27.8 ft. S9,NBT |
| Corner E3: Drove 1" I.D.x32" iron pipe in center of east-west road.
7" Sugar S28E 12.6 ft. S9,NBT
8" Sugar N57W 35.5 ft. S5,NBT
10" Sugar N41E 26.8 ft. S4,NBT | Corner F3: Set 1" I.D.x32" iron pipe with 4" alum. cap.
14" Sugar N39E 21.0 ft. 1/4S,NBT
6" Sugar S38E 25.6 ft. 1/4S,NBT
5" Sugar N24W 8.3 ft. 1/4S,NBT
4" Sugar squared S05E 3.0 ft. |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006