

BARAGA Co.

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... T. 49 N. R. 32 K. W. C9, C8
2. PROPERTY CONTROLLING IN SECTION 19, T. 49 N. R. 32 K. W. 14
3. MISCELLANEOUS PROPERTY IN SECTION... T. ... N. S., R. ... E. W.
4. LOT NO. ... , RECORDED PLAT ...
5. PRIVATE CLAIMS ...

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 29 & July 3, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on ..., 19..., found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner C9: Original Monument and accessories Not Found. Found old scribed Sugar not original by unknown persons.
Corner C8: Found old blazes and two stumps which match for species, bearing and distance of original bearing tree. Located 1957 by K. D. Killmer.
Corner 14: Not Set on Original Survey Nor Subsequently Apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner C9: Re-established on 7-3-78 by old scribed tree. Checks with corners North and South. Has been used as corner for many years.
Corner C8: Re-established on June 29, 1978 from old blazes and two stumps which match for species, bearing and distance of original bearing tree.
Corner 14: Established on 7-3-78 on line between corners north - south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner C8: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap. 18" White Pine S22E 13.8 ft. 1/4S, NBT 18" White Pine N75E 17.1 ft. 1/4S, NBT 7" Maple N66W 19.1 ft. 1/4S, NBT
Corner C9: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap. 7" Sugar S66E 12.7 ft. S29 NBT 14" Sugar N45E 5.0 ft. S20 NBT 10" Maple S72W 11.2 ft. S30 NBT
Corner 14: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap. 6" Cedar N37W 8.2 ft. 1/16S BT 5" Cedar N53E 15.3 ft. 1/16S BT 5" Balsam S40W 2.6 ft. 1/16S BT 6" Maple Squared S38W 1.7 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett, Michigan Registered Land Surveyor, Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

