

BARAGA CO.

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 49 N. 32 W. S. R.	B9
2. PROPERTY CONTROLLING IN SECTION 30 _____	T. 49 N. 32 W. S. R.	7, 2 & 1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner 7: Not Set on Original Survey Nor Subsequently Apparently.
  - Corner 2: Not Set on Original Survey Nor Subsequently Apparently.
  - Corner 1: Not Set on Original Survey Nor Subsequently Apparently.
  - Corner B9: Original Monument and Accessories Not Found. Found old downed post which fits good with land calls and alignment between section corners.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner 7: Established 7-5-78 on line between corners north and south. Numerous old blazes in area.
  - Corner 2: Established 7-11-78 on line between corners east and west.
  - Corner 1: Established 7-11-78 on line between corners east and west.
  - Corner B9: Re-established 7-11-78 at old post location. This post fits good with all other evidence.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner 7: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.  
4" Sugar N80W 8.0' 1/16S, BT  
8" Sugar EAST 5.4' 1/16S, BT  
15" Sugar S03W 19.3' 1/16S, BT
  - Corner 1: Set 1" I.D. x 36" Iron Pipe with aluminum cap.  
8" Sugar S35E 10.3' 1/16S, BT  
5" Sugar N69E 22.0' 1/16S, BT  
7" Sugar N54W 22.2' 1/16S, BT
  - Corner 2: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.  
4" Sugar N11E 15.6' 1/16S, BT  
3" Sugar S30W 3.0' 1/16S, BT  
10" Yellow Birch S63E 5.2' 1/16S, BT
  - Corner B9: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.  
5" Spruce N49W 7.2' 1/2S, NBT  
9" Spruce S74W 22.7' 1/2S, NBT  
3" Spruce S44E 11.7' 1/2S, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE July 18, 1978

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
Keith L. Sackett  
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET