

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 11 T 49N R 32W _____	8
	S 11 T 49N R 32W _____	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 11 06/07/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 11) West 1/16 corner, Section 11. Not established in the original survey.

(11-Sec. 11) Southwest 1/16 corner, Section 11. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 11) Established the corner midway and on a straight line between Quarter corner 1330.13' west and the Center of Section 11 1330.13' east.

(11-Sec. 11) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The position for the corner falls on the easterly bank of the Silver River, about 2' SE of the top of the bank.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 10" Sugar S52E 28.3' mrkd "1/16S BT"
 10" Sugar S07E 20.1' do
 5" Sugar N78W 22.75' do
 6" Sugar N43W 17.25' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" Spruce S75E 41.15' mrkd "1/16S BT"
 5" Spruce S48E 29.4' do
 15" Spruce S13E 32.1' do
 6" Spruce S16W 36.65' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 07/27/2011

For the Michigan Department of Natural Resources, Forest Management Division

