

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 32W	E7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 20 T 49N R 32W	2
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 15 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (E7) Corner common to Sections 16-17-20-21. Corner established in 1852 by Guy H. Carleton: "...Corrected between Secs. 17 & 20...80.00 Set post corner of Secs 16-17-20-21, Spruce 8 N21E 15 lks, White Pine 20 N50W 43 lks". Corner recovered in 1854 by U.S. Examination survey: "...Section corner Fir 10 N23E 14.5 lks, White Pine 30 N53W 42 lks." July 10, 1944 notes of N.T.Thompson, RLS: "set cedar post acc. to old pine down". Corner recovered in 1993 by R.W.Crampton, PS24591, "1" iron pipe (fnd.) witnessed with survey tag nailed to: 6" Balsam tree N51W 15.38', 13" Maple tree N54E 33.48', 6" Maple tree S33E 26.00', 16" Maple tree S70W, 23.63".
 (2-Sec. 20) East 1/16 corner between Sections 17-20. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E7) Original post and accessories were not recovered. Found a 1" ID iron pipe projecting 3.5' above ground, in good condition, and at record bearing and distance from the 1993 witnesses noted above. Also recovered a Ford Motor Co. metal location poster facing the corner (probably Thompson's), and an old blazed cedar stub N52W 7.1' facing the pipe. Accepted the pipe as the best available evidence of the position of the original corner. Left the pipe in place, remeasured the 1993 witnesses, and made one new NBT, as described below.

(2-Sec. 20) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Quarter corner 1290.36' West and Section corner 1290.36' East. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E7) Found 1" ID iron pipe. Found washer with meas. nail in the following blazed trees:	(2) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following:
12" Sugar N56E 33.55'	7" twin Sugar N18E 14.5' "1/16S BT"
7" Sugar (dead) S32E 26.1'	9" Sugar S52E 36.1' do
14" Sugar S66W 23.60'	6" Sugar N87W 22.3' do
6" Balsam N54W 15.33'	11" Sugar N35W 32.1' do
Blazed and scribed the following:	Placed a squared sugar post adjacent.
16" Cedar S60E 39.0' "S21 NBT". Dist. to measuring notch. All brgs. are magnetic.	Dist. are to notch in lower blaze. Brgs. are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/1/99

For the Michigan Department of Natural Resources - Forest Management Division