

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>49N</u> R <u>32W</u>	H3	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S <u>10</u> T <u>49N</u> R <u>32W</u>	2	
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

2 Jun 06 2002
 H3 Jun 03 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5			4		3		2		1
3									●				
4		7		8			9		10		11		12
5													
6		18		17			16		15		14		13
7													
8		19		20			21		22		23		24
9													
10		30		29			28		27		26		25
11													
12		31		32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (H3) Quarter corner common to Sections 3-10. 1852: Established by Guy H. Carleton: "...40.00 Set quarter post. Cedar 16 S51W 25 links, Cedar 24 N40W 17 links".
 (2-Sec. 10) East 1/16 corner between Sections 3 and 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (H3) The original post was not recovered. Remonumented the corner at record bearing and distance from the remains of the OBT Cedar S51W 25 links, now a well rotted windfall with traces of face and scribing visible. The tree has fallen directly upon the corner position. At record bearing and distance for the NW OBT, found a mound of soil, possibly the remains of the root plate of a windthrow. The monumented position is S38E 13' from the proportionate position between Section Corners.
 (2-Sec. 10) Established the corner midway and on a line of mean true bearing between quarter corner 1301.79' west and section corner 1301.79' east. The position for the corner falls in a beaver flooding and was not monumented. Established a WITNESS CORNER on the section line 100.00' east of the 1/16 corner. The beaver flooding is about 10 acres in size. The witness corner described herein is about 5' NE of the water's edge. The monument, made firm in a mound of rock 3.5' dia.x2' high, rests on bedrock about 9" below ground surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (H3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
 10" Sugar N26W 20.1' "1/4S NBT"
 10" Sugar S72E 25.0' do
 14" Maple S14E 7.5' do
 8" Sugar S66W 19.1' do
 Placed a squared sugar post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.
 (2-Sec. 10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap 100.00' east from the 1/16 corner position and on the section line. Blazed and scribed:
 10" Cedar S69E 22.5' "WC BT"
 17" W.Pine S47E 25.0' do
 9" Cedar N34W 9.4' do
 7" Cedar N02E 7.3' do
 Set a squared cedar post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 7/11/02
 Surveyor's Michigan License No. 33986