

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------------------|-----------|
| 1. Public Land Survey | T <u>49N</u> R <u>32W</u> | <u>F7</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S <u>16</u> T <u>49N</u> R <u>32W</u> | <u>2</u> |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 12 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(F7) Quarter corner common to Sections 16-21. 1852: Established by Guy H. Carleton. "Corrected between 16 & 21...40.00 Set quarter post. Sugar 8 NW 12 links, Sugar 16 South 17 links...80.00 set post corner of Secs 15-16-21-22". 1854: Examiner's notes (name not known) state: "West between 16 and 21...40.66 Quarter corner. Maple 16 S4E 16, Sugar 8 N5W 11, Random 3.00 porth...80.77 Section corner".

(2-Sec. 16) East 1/16 corner between Sections 9 and 16. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F7) The original post and accessories were not recovered. At a position N17E 9.4 ft. distant from Carleton's position, proportioned to his record between Section corners, find a 1" ID iron pipe, projecting 29" a.g. Accept same as the best available evidence of the position of the original corner. Placed a yellow plastic cap stamped "MICH DNR PS33986" into the top of the pipe. The pipe leans slightly to the SE but is firmly set.

(2-Sec. 16) Established the corner midway and on a line of mean true bearing between 1/4 corner 1308.78' west and Section corner 1308.78' east. From the corner thus established, I found an iron pipe, not of record N75E 2.4' distant. Several other pipes were found near to 1/16 corners in Sec. 16. Their proximity to the proper corners ranges up to a maximum of 51'. I believe them to be approximate corner positions, set by improper procedures, and did not accept any of them.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F7) Found a 1" ID iron pipe. Placed plastic cap #33986 into it. Blazed and scribed:	(2) Set 1" ID x 32" I. pipe with 4" alum. MDNR cap. Blazed and scribed:
9" Sugar N60E 11.6' "1/4S N8T"	5" Sugar N28E 12.4' "1/16S BT"
5" Sugar S05W 21.0' do	13" Sugar S59E 31.2' do
7" Sugar S38W 21.4' do	7" Sugar S60W 21.7' do
8" Sugar N13W 16.7' do	6" Sugar N51W 16.3' do
Set squared spruce post adjacent.	Set squared cedar post adjacent.
Bearings are magnetic. Distances are to notch in lower blaze.	Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/11/02