

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

 (County)

Located in:

Corner Code #

1. Public Land Survey	T <u>49N</u> R <u>32W</u>	H4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>16</u> T <u>49N</u> R <u>32W</u>	9
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

H4 Jun 10 2002

9 Jun 12 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		●		11		12		
5													
6	18		17		16	●	15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H4) Center of Section 10. Not established in the original survey.

(9-Sec. 16) East 1/16 corner, Sec. 16. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(9-Sec. 16) Established the corner midway and on a straight line between Center of Section 1308.53' west and 1/4 corner 1308.53' east. From the corner thus established, I found an iron pipe, not of record, S68E 6.3' distant, which I did not accept as marking the position for the corner, believing it to be someone's approximation of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H4) Set 1"IDx32" I.pipe with 4" alum.

MDNR cap. Blazed and scribed:

19" Cedar N10W 51.0' "C1/4 BT"

10" Spruce N49E 25.2' do

14" Cedar N89E 33.4' do

14" Spruce S15E 22.6' do

Placed a sq'd cedar post adjacent.

Bearings are magnetic. Distances are to notch in lower blaze.

(9) Set 1"IDx32" I.pipe with 4" alum.

MDNR cap. Blazed and scribed:

8" Sugar N67E 24.4' "1/16S BT"

11" Sugar S18E 16.2' do

17" Hemlock S25W 8.5' do

9" Hemlock N83W 33.9' do

Set squared cedar post adjacent.

Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/11/02