

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------------------|-----------|
| 1. Public Land Survey | T <u>49N</u> R <u>32W</u> | <u>F5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>16</u> T <u>49N</u> R <u>32W</u> | <u>16</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

16 Jun 18 2002
 F5 Jun 11 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5						●							
6		18		17		16		15		14		13	
7						●							
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F5) Quarter corner common to Section 9 & 16. 1852: Established by Guy H. Carleton: "Corrected between 9 & 16...40.05 Set quarter post. White Pine 14 S31W 43 links, Maple 8 N31E 34 links... 80.10 Section corner".
 (16-Sec. 16) East 1/16 corner between Sections 16 and 21. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F5) The original post and accessories were not recovered. Found a 1" ID x48" iron pipe which appears to have been accepted by the local landowners as marking the position of the corner. A 1985 forestry location poster faces the pipe and blue paint lines extend to the south and east. The GLO position, proportioned between Section Corners is N27W 8.6'. I accept the pipe as the best available evidence of the position of the original corner and make it firm in a mound of rock 3.5' dia. x 2' high.
 (16-Sec. 16) Established the corner midway and on a line of mean true bearing between 1/4 corner 1308.33' west and Section corner 1308.33' east. From the corner thus established, I found a 1" ID iron pipe S5W 51.4' distant which I did not accept as marking the corner position, believing it to be someone's approximation of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F5) Found a 1"x48" iron pipe. Blazed and scribed:	(16) Set 1" ID x 32" I. pipe with 4" alum. MDNR cap. Blazed and scribed:
5" Sugar N02E 5.8' "1/4S N8T"	5" B. Spruce N10E 43.1' "1/16S BT"
10" Sugar N79E 12.0' do	5" Cedar N71E 48.6' do
5" Sugar S63E 9.2' do	6" Cedar S70E 44.5' do
7" Cedar S67W 9.4' do	7" Tamarack N12W 69.8' do
Bearings are magnetic. Distances are to notch in lower blaze.	Set a squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/11/02