

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

 (County)

Located In: _____ Corner Code # _____

- | | | | |
|------------------------------------|---------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>49</u> N | R <u>32</u> W | D6 |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S <u>16</u> | T <u>49</u> N R <u>32</u> W | 12 |
| | S _____ | T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 18 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		●		16		15		14		13	
7					●							
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (D6) Center of Section 17. Not established in the original survey. Found no subsequent record.
 (12-Sec. 16) South 1/16 corner, Section 16. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (D6) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. From the position thus established, found a 1" ID iron pipe, not of record, S88E 104.6' distant. The found pipe is at the corner of an ill-defined barbed wire fence which runs north and west from the pipe. I cannot account for the great difference between the location of this pipe and the proper center of this section and I do not accept the pipe as marking the position of the corner.
 (12-Sec. 16) Established the corner midway and on a straight line between Center of Section 1294.38' north and 1/4 corner 1294.38' south. From the position thus established, found a 1" ID iron pipe, not of record, N66E 5.3' distant, which I did not accept for the corner, believing it to be someone's approximation of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| (D6) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
5" Sugar N54E 7.7' "1/4 BT"
8" Sugar S03W 20.3' do
6" Sugar N81W 28.1' do
7" W.Pine N32W 18.1' do
The last is adjacent to a 28" W.Pine.
Set a squared cedar post adjacent.
Bearings are magnetic. Distances are to notch in lower blaze. | (12) Set 1" IDx32" I.pipe with 4" alum. MDNR cap made firm in a small mound of rock. Blazed and scribed:
5" Sugar N16E 11.1' "1/16S BT"
11" Sugar S41E 18.5' do
11" Sugar S45W 8.3' do
11" Sugar N37W 31.1' do
Placed a squared cedar post adjacent.
Bearings are magnetic. Distances are to notch in lower blaze. |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|



Signed by Stephan J. Szyszkoski Date 7/11/02
 Surveyor's Michigan License No. 33986