

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 32W	G12
	T 49N R 32W	H13
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

H13 Apr 21 2005
 G12 Oct 26 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (G12) Quarter corner common to Sections 33-34. 1852: Established by Guy Carleton, Deputy Surveyor midway between Section corners 40.05 chains north and south. BTs: Spruce 6 N58E 40 links, Tamarack 6 N82W 53 links. 1948: N.T.Thompson notes he found tamarack BT "OK stub", and "set ced post New B.T.s spr. 6 S68E 8.6, spr 7 S87W 18.0"
 (H13) Quarter corner common to Section 34 T49N-R32W and Section 3 T48N-R32W. 1846: Established by W.A.Burt: West on South side Sec. 34 ...40.00 Set Sugar post qr. Section Corner. Spruce 10 East 1 link, Sugar 6 N27W 16 links. ... 80.00 Set Sugar post corner of Secs. 33 and 34.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G12) Found a squared and scribed post, believed to be that set by N.T.Thompson, at record bearing and distance from the stump remains of the original BT Tamarack N82W 53 links, now well rotted. Distances north and south to adjacent section corners are 2632.09' and 2667.13', respectively. The post is 32' east of a straight line between them. I note that my experience in this township shows that Mr. Carleton's work was rather loose. I accept the post as a careful and faithful perpetuation of the position of the original corner. Replaced same with a new monument, as described below.
 (H13) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway between Section corners 2633.19' East and West and on the curved township line of constant true bearing (rhumb line) between them.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 4" B.Spruce N21W 17.0' mrkd "1/4S NBT" 4" B.Spruce N86E 9.7' do 4" W.Pine S15E 14.6' do 4" B.Spruce S66W 7.0' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(H13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Cherry N72E 16.7' mrkd "1/4S NBT" 10" Spruce S15E 14.3' do 7" Cedar S27W 27.6' do 17" W.Pine N18W 48.8' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/13/05