

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 32W	I13
	T 49N R 32W	I11
2. Property Controlling in Section	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I11 Nov 08 2004
 I13 Nov 04 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (I13) Corner common to Sections 34-35 T49N-R32W and Sections 2-3 T48N-R32W. 1969: Remonumented by A.O. Enger RLS in the original position as determined from 2 original BTs: Cedar 18 S70W 18, in good condition with all iron marks visible, and Cedar 12 N47W 58, dead and down. Set 1"IDx36" iron pipe with 4" alum. cap. New BTs: Cedar 15 S52E 29.5 links, Cedar 8 S42 1/2W 31 links.
 (I11) Corner common to Sections 26-27-34-35. 1852: Established by Guy Carleton, Deputy Surveyor: "N6'W corrected between Sections 34 & 35 ... 80.20 Set post corner of Secs. 26-27-34-35. Sugar 10 S12E 27 links, Sugar 12 N24W 21 links. ... Between Secs. 26 & 27 ... 17.16 Intersect South Boundary of lake and set meander post". Record distances to G11 and L11 from I11 are 79.60 chains and 120.29 chains, respectively. Found no other record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (I13) Found the 1969 monument disturbed by a fallen tree. Re-set the 1969 monument at the record position by distances to the 1969 NBTs and the original Cedar BT S70W (measured mag. bearing N86W) 18 links. I noted some variance between the record bearings and our magnetic bearings to the previous witnesses and did not place too great a weight on the record bearings in remonumenting the corner. The original Cedar BT rec. S70W is still in good condition with scribing and notch plainly visible.
 (I11) Found an old 1.5" ID iron pipe with old double blazes and location poster facing. Distances north to lake edge (meander corner was not found) 1108' (1133' R), Corner G11 of record 5220' (5254' R) and to a pipe at L11 approx. 7901' (7939' R), are all in reasonable accord with the original record. Accepted the 1.5" pipe as the best available evidence of the position of the original corner. I note that the distance I11-I13 is 5375.14 (82' longer than record). My experience in this township is that the original survey is somewhat defective and I am not surprised to see a deviation from the record of that magnitude.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (I13) Reset 1969 1"ID I.pipe with 4" alum. cap and made firm with rock. Set measuring nails in:
 22" Cedar N86W 11.9' original BT
 12" Cedar S45W 20.4' scribing plain *
 18" Cedar S45E 19.5' faces punky *
 Bearings are magnetic. Distances are to nail with tag. * denotes 1969 NBT
 (I11) Drove 1"IDx32" I.pipe with 4" alum. MDNR cap into fd. 1.5" ID I.pipe. Set measuring nails in:
 7" Sugar N72E 21.5' mrkd "S26 NBT"
 10" dbl Sugar N05E 11.9' do
 26" W.Pine S17E 24.2' "S35 NBT"
 8" Sugar S85W 19.1' "S34 NBT"
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/13/05