

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u>	<b>Located In:</b>	<b>Corner Code #</b>	
<small>(County)</small>			
<b>1. Public Land Survey</b>	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
<b>2. Property Controlling in Section</b>	S <u>34</u> T <u>49N</u> R <u>32W</u>	<u>4</u>	
	S <u>34</u> T <u>49N</u> R <u>32W</u>	<u>8</u>	
<b>3. Miscellaneous Property in Sec.</b>	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 02 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (4-Sec. 34) Northwest 1/16 corner, Section 34. Not established in the original survey.  
 (8-Sec. 34) West 1/16 corner, Section 34. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(4-Sec. 34) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.  
 (8-Sec. 34) Established the corner midway and on a straight line between Quarter corner 1294.82' west and Center of Section 1294.82' east. The position for the corner falls on a south-facing slope. Made the monument firm in a 1.5' dia. mound of rock.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Spruce N50E 11.6' mrkd "1/16 S 8T" 5" Spruce S20W 16.7' do 4" Spruce S67W 6.2' do 4" Tamarack N50W 20.7' do Set sq'd tam. post adjacent. Bearings are magnetic. Distances are to nail with tag.	(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 10" W.Pine S17E 10.9' mrkd "1/16S 8T" 6" Cedar S50W 8.3' do 5" Sugar N67W 13.0' do 7" Cedar N08W 33.1' do Set sq'd tam. post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/13/05