

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	<u>34</u>	T	<u>49NR</u> <u>32W</u>	<u>11</u>
3. Miscellaneous Property in Sec.	S	<u>34</u>	T	<u>49NR</u> <u>32W</u>	<u>10</u>
	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 27 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (11-Sec. 34) Southwest 1/16 corner, Section 34. Not established in the original survey.
 (10-Sec. 34) South 1/16 corner between Sections 33-34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 34) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (10-Sec. 34) Established the corner midway and on a straight line between Section corner 1333.57' south and Quarter corner 1333.57' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 12" Sugar N19W 11.5' mrkd "1/16S BT" 10" Sugar N89E 15.8' do 18" W.Pine S29W 10.1' do 16" W.Pine N66W 21.0' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Sugar N50W 19.0' mrkd "1/16S BT" 11" Sugar S79E 18.7' do 13" Sugar S23W 15.3' do 8" Sugar N81W 26.5' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/13/05