

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| Baraga | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T 49N R 32W | A9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on 09/22/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A9) Corner common to Sections 19-30 T49N-R32W and Sections 24-25 T49N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. Set Fir post. Tamarack 7" S66E 53 links, Spruce 10" N33W 26 links. 1977 - Original corner not found. Reestablished by K.L.Sackett RLS from "land calls and other corners". Set 1" IDx36" Iron pipe with 4" aluminum cap. 16" W.Pine N89W 12.6', 6" Cedar S56E 47.5', 5" Spruce S20W 20.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A9) Found the 1977 monument in good condition and at record bearing and distance from the 1977 witnesses. The W.Pine NW is in good condition with scribing visible, The Cedar SE is standing dead, and the Spruce SW is dead and down. The monument is 5282.41' south (GLO=5280'), but only 5201.39' north (GLO=5280') of adjacent section corners. I note that the distance from A9 to A13 was found to be 126.1' shorter than the GLO record, making both miles between this corner and the township corner to the south substantially shorter than the GLO record. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A9) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 15" W.Pine N83W 13.25' old marks 1977 NBT
 4" B.Spruce N68E 30.9' mrkd "S19 NBT"
 4" B.Spruce S52W 13.1' "S25 NBT"
 5" Cedar N30W 11.7' "S24 NBT"
 Set sq'd cedar post adjacent.
 Bearings are magnetic.



Signed by *Stephan J. Szyszkoski* Date 10/23/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities