

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 32W	B9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 09/22/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B9) Quarter corner common to Sections 19 and 30. 1852 - Established by Guy Carleton Deputy Surveyor on the Section line between Section corner 40.00 chains east and Section corner 35.25 chains west. Set post. Spruce 6" S30W 38 links. 1978 - Remonumented by K.L.Sackett RLS at position of an old post found down on the ground which fit good with land calls and alignment between section corners. Set 1"IDx36" I.pipe with 4" aluminum cap. 5" Spruce N49W 7.2', 9" Spruce S74W 22.7', 3" Spruce S44E 11.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B9) Found the 1978 monument in good condition and at record bearing and distance from the 1978 NBTs Spruce SW in good condition, and Spruce NW, now a stump. The NBT Spruce SE was not apparent above the moss. Accepted same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B9) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" B.Spruce S79W 23.1' old marks 1978 NBT
 2" Tamarack N45E 20.3' mrkd "1/4S NBT"
 4" B.Spruce S17E 11.1' do
 4" Tamarack S41W 14.0' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/23/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities