

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 32W	C13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/25/2005 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C13) Section corner on the Township line common to Sections 31-32 T49N-R32W and Sections 5-6 T48N-R32W. Remonumented by K.L.Sackett RLS in 1977 at the position of an old post found "in a rock pile that fits good with land calls N-S-E-W, and possible line tree west". Set 1"IDx36" iron pipe with 4" aluminum cap. 5" Yellow Birch N63W 5.9', 7" W.Pine N78E 6.0', 12" Balsam S75W 11.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C13) Found the 1977 monument in good condition and at record bearing and distance from the 1977 NBTs. The W.Pine NE is in good condition with overgrown blazes, the Y.Birch NW is in good condition with scribing visible, the Balsam SW is standing dead with scribing plain. The position of the monument checks well with the original GLO record to monumented Township corner 4971.28' N89 deg. 48'59"W (GLO=4985') and reestablished Section corner 5276.08' S89 deg. 38'53"E (GLO=5280') - true bearings. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C13) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 15" W.Pine N83E 6.2' old blazes 1977 NBT
 8" Y.Birch N60W 6.2' old marks do
 7" B.Spruce S77E 12.3' mrkd "S5 NBT"
 12" W.Spruce N79W 39.4' "S31 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 12/09/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities