

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 32W	C10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 09/22/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C10) Quarter corner common to Sections 29-30. 1852 - Established by Guy Carleton Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. B.Ash 6" S65W 25 links, B.Ash 6" S88E 54 links. 1971 - A.O.Enger RLS remonumented the corner at record bearing and distance from an original Black Ash bearing tree. Set 1"IDx36" iron pipe with 4" aluminum cap. Y.Birch 5" S05W 11.1', Y.Birch 13" N36E 18.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C10) Found the 1971 monument in good condition and at record bearing and distance from the 1971 NBTs, the Y.Birch NE now a dead stub, the Y.Birch SW in good condition with scribing visible, and at record bearing and distance from the remains of the original B.Ash BT S67W 16.5' distant, now a 20" dia. hollow 5' high stump with old open faces. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C10) Fd. 1"ID I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 6" Y.Birch S08W 11.3' old marks 1971 NBT
 4" Maple N34E 24.2' mrkd "1/4S NBT"
 10" B.Ash S67E 29.0' do
 6" Y.Birch N54W 14.4' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/23/2008
 Surveyor's Michigan License No. 33986