

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 32W	A11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 09/21/2005 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A11) Corner common to Sections 30-31 T49N-R32W and Sections 25-36 T49N-R33W. 1846 - Established by Austin Burt Deputy Surveyor on the Range Line between R33W and R32W. Set Cherry post. Fir 14" S10E 58 links, Spruce 8" N38W 50 links. 1852 - Additional BT by Z.B.Searles Deputy Surveyor Fir 14" S65W 58 links. 1988 - K.L.Sackett RLS remonumented the corner at the position of an old squared cedar post found. Set 1"IDx32" I.pipe with 4" alum. cap. 24" Cedar S33W 9.0', 24" Spruce N52E 28.9', 4" Maple N41W 29.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A11) Found the 1988 monument in good condition and at record bearing and distance from the 1988 witnesses. The Spruce NE is dead and down with scribing visible. The Cedar SW was cut down this date to facilitate GPS observations. The NW BT is a Sugar and is in good condition. Found the monument to be 5227.3' north and 5207.4' south of adjacent Section corners. Accepted same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A11) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Y.Birch clump N81E 13.7' mrkd "S30 NBT"
 9" Spruce S51E 26.3' "S31 NBT"
 17" Sugar N81W 66.3' "S25 NBT"
 5" Sugar N41W 29.6' old marks 1988 NBT
 Sq'd post adjacent. Bearings magnetic.



Signed by Stephan J. Szyszkoski Date 10/23/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities