

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>49N</u> R <u>32W</u>	<u>C11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 09/26/2005 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C11) Corner common to Sections 29-30-31-32. 1852 - Established by Guy Carleton Deputy Surveyor. Set post. Sugar 12" N64W 34 links, Sugar 10" S66E 16 links. 1976 - Reestablished by K.L.Sackett RLS by double proportionate measurement between land calls north, south, east, and west. Set 1"IDx36" iron pipe with 4" alum. cap. 7" Sugar S84W 3.5', 7" Sugar S48E 5.8', 12" Sugar N48E 6.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C11) Found the 1976 monument in good condition and at record bearing and distance from the 1976 NBTs with the exception of the NBT Sugar S84W which is actually N85W from the corner. The Sugar SE is in good condition, the Sugar NE is dead and down with scribing visible. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C11) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Sugar S46E 6.0' old marks 1976 NBT
 10" Sugar N85W 3.8' do do
 8" Sugar N10E 16.4' mrkd "S29 NBT"
 12" Sugar N71E 20.2' do
 Sq'd post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/23/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities