

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 32W	C12
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 09/07/2005 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C12) Quarter corner common to Sections 31 and 32. 1852 - Established by Guy Carleton Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Yellow Birch 12" N20W 19 links, Fir 8" N52E 36 links. 1988 - K.L.Sackett RLS reestablished the corner midway and on a straight line between Section corners north and south. Set 1"IDx36" I.pipe with 4" aluminum cap. 12" W.Pine S82W 22.1', 14" W.Pine S25W 18.3', 11" Sugar S42E 6.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C12) Found the 1988 monument of record in good condition and at record bearing and distance from the 1988 witnesses. The Sugar SE was cut down this date to facilitate GPS observations, the two W.Pines are in good condition. Verified the position of the monument and found it to be 0.2 ft. east of a straight line between Section corners 2616.47 ft. south and 2616.91 ft. north. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C12) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Sugar N34W 18.7' mrkd "1/4S NBT"
 8" Sugar N40E 17.2' do
 16" W.Pine S27W 18.4' old marks 1988 NBT
 15" W.Pine S83W 22.3' do do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/23/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities