

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 30 T 49N R 32W	2
	S 30 T 49N R 32W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 09/22/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(2-Sec. 30) East 1/16 corner between Sections 19 and 30. 1978 - Established by K.L.Sackett RLS on line between corners east and west. Set 1"IDx36" iron pipe with 4" alum. cap. 4" Sugar N11E 15.6', 3" Sugar S30W 3.0', 10" Y.Birch S63E 5.2'.

(12-Sec. 30) South 1/16 corner, Section 30. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(2-Sec. 30) Found the 1978 monument in good condition and at record bearing and distance from the 1978 witnesses. The Sugar NE is standing dead, the Sugar SW and Y.Birch SE are in good condition. I accept the monument as a careful and faithful establishment of the position of the corner. Made the monument firm in a mound of rock.

(12-Sec. 30) Established the corner midway and on a straight line between Quarter corner 1290.15' South and Center of Section 1290.15' North. The position for the corner falls in an inaccessible area and was not monumented. Established a Witness Corner, on the N-S 1/4 line, 187.00' south of the position for the corner. Monument was made firm in a mound of rock.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(2) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" twin Y.Birch S57E 5.6' old marks 1978 BT  
 4" Sugar S32W 3.2' do do  
 3" Sugar N25E 16.65' mrkd "1/16S BT"  
 4" Sugar N68W 24.5' do  
 Set Sq'd cedar post near.  
 Bearings are magnetic.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap for a Witness Corner 187.00' south of the corner position. Set measuring nail with MDNR tag in the side of:  
 3" Sugar S81E 1.5' mrkd "WC BT"  
 3" twin Hemlock S74E 7.0' do  
 16" Cedar S42W 21.0' do  
 Cedar N06E 22.1' do  
 Sq'd post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/23/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities

16153  
16151