

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 30 T 49N R 32W	3
	S 30 T 49N R 32W	14
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 09/22/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(3-Sec. 30) North 1/16 corner between Section 30 T49N-R32W and Section 25 T49N-R33W. 1990 - Established by K.L.Sackett RLS midway and on line between Section and Quarter corners. Set 1"IDx36" iron pipe with 4" aluminum cap. 24" Cedar S86E 31.0', 4" Sugar N22W 8.2', 7" Sugar S52W 6.5'.

(14-Sec. 30) South 1/16 corner between Sections 29 and 30. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(3-Sec. 30) Found the 1990 monument in good condition and at record bearing and distance from the 1990 witnesses. The Cedar SE is in good condition, the Sugar SW is a dead stub, and the Sugar NW has been cut down by beavers. Verified the position of the monument and accepted same as a careful and faithful establishment of the position of the corner.

(14-Sec. 30) Established the corner midway and on the Section line between Section corner 1308.19' South and Quarter corner 1308.19' North.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(3) Fd. 1"ID I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 20" Cedar S86E 32.0' old marks 1990 BT  
 18" Maple N33E 18.4' mrkd "1/16S BT"  
 6" Sugar S40W 28.5' do  
 22" Y.Birch N14W 15.0' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 12" Sugar N16E 21.3' mrkd "1/16S BT"  
 9" Hemlock S54E 9.9' do  
 14" Sugar S75W 12.0' do  
 5" Sugar N24W 13.0' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/23/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities