

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T 49N R 32W	B8
	S 19 T 49N R 32W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	•	20	21	22	23	24							
9	•												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 09/15/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(B8) Center of Section 19. Not established in the original survey.

(12-Sec. 19) South 1/16 corner, Section 19. Not established in the original survey. Corner established by Robert W. Crampton RLS during a survey of the S1/2 of the SE1/4 of Section 19, unknown date. Set 1/2" iron pipe with red plastic cap stamped LLS 24591.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(B8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(12-Sec. 19) Found the R.W.Crampton monument in good condition and accepted same as a careful and faithful establishment of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

<p>(B8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:          10" Sugar N17E 12.5' mrkd "C1/4 BT"          7" Sugar N82E 21.0' do          8" Y.Birch South 13.9' do          9" Y.Birch S31W 11.95' do          Set sq'd cedar post adjacent.          Bearings are magnetic.</p>	<p>(12) Fd. 1/2" I.pipe with plastic cap stamped "LLS 24591". Set meas. nail with MDNR tag in the side of:          14" Hemlock N03E 32.35' mrkd "1/16 BT"          4" Sugar S02E 35.0' do          5" Sugar N82W 20.7' do          6" Sugar N38E 5.55' RWC nail facing cor.          Set sq'd cedar post adjacent.          Bearings are magnetic.</p>
--	---

Signed by Stephan J. Szyszkoski Date 10/23/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

