

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>30</u> T <u>49N</u> R <u>32W</u>	<u>1</u>
	S <u>30</u> T <u>49N</u> R <u>32W</u>	<u>4</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 1 09/15/2008
4 09/17/2008 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 30) West 1/16 corner between Sections 19 and 30. Not established in the original survey. 1978 - K.L.Sackett RLS established the corner on line between corners east and west. Set 1" IDx36" iron pipe. 8" Sugar S35E 10.3', 5" Sugar N69E 22.0', 7" Sugar N54W 22.2'.

(4-Sec. 30) Northwest 1/16 corner, Section 30. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 30) Found the 1978 monument and accessories in good condition, but 21 ft. west of the proper position. Removed the monument and reestablished the corner on the Section line between Quarter corner 1376.51' east and Section corner 1049.59' west. This position is 20 chains west of the Quarter corner, and 15.25 chains east of the Section corner, proportionate to the dimensions given on the face of the original plat.

(4-Sec. 30) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| <p>(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 7" Sugar N79E 8.9' mrkd "1/16S BT"
 9" Sugar S16E 8.85' do
 12" Sugar S63W 15.1' do
 10" Sugar N01W 16.9' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.</p> | <p>(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 10" Sugar N08W 32.2' mrkd "1/16S BT"
 6" Sugar N85W 22.55' do
 4" Sugar S31W 19.2' do
 6" Sugar S42E 12.2' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.</p> |
|---|--|

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/23/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities