

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| Baraga | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S 30 T 49N R 32W _____ | B10 |
| | S 30 T 49N R 32W _____ | 5 |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 20 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on 09/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B10) Center of Section 30. Not established in the original survey.

(5-Sec. 30) North 1/16 corner, Section 30. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B10) Established the corner at the intersection of straight lines connecting opposite Quarter corners. The position for the corner falls on a nearly vertical rock outcrop about 3 ft. above a ledge. The corner monument pipe was bent to conform to the rock face and was made firm with a mound of rock 4.5' long x 3.4' wide x 2.3' high. The center of the monument cap marks the corner position.

(5-Sec. 30) Established the corner midway and on a straight line between Center of Section 1312.93' south and Quarter corner 1312.93' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 13" Sugar N15W 10.1' mrkd "C1/4 BT"
 5" Sugar S78E 12.9' do
 11" Sugar S18W 16.9' do
 14" Sugar S79W 16.35' do
 Set sq'd cedar post near.
 Bearings are magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Maple N75E 19.5' mrkd "1/16S BT"
 5" Maple S85E 18.25' do
 12" Y.Birch S58W 32.0' do
 9" Spruce S73W 15.8' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 10/23/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities