

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 32 T 49N R 32W _____	D12
	S 32 T 49N R 32W _____	14
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

D12 12/11/2008

I, Stephan J. Szyszkoski, in a field survey on 14 12/16/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(D12) Center of Section 32. 1988 - monumented by K.L.Sackett RLS at the intersection of 1/4 lines. Set 1"IDx36" I.pipe with 4" aluminum MDNR cap. 10" Sugar S36E 27.2', 16" Cedar N15W 7.8', 12" Balsam S55E 17.1'.

(14-Sec. 32) South 1/16 corner between Sections 32 and 33. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(D12) Found but did not accept the 1988 monument. The 1988 Quarter corners D13 and E12 have been reestablished at corrected positions, rendering the 1988 position for D12 incorrect. Established the corner at the intersection of straight lines connecting opposite 1/4 corners, D13 and E12 having been reestablished and monumented by the undersigned. Removed the 1988 monument, which was found N38W 24.2' distant.

(14-Sec. 32) Established the corner midway and on the Section line between Quarter corner 1323.71' north and Section corner 1323.71' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(D12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 19" Cedar N28W 32.8' old marks 1988 BT  
 26" Hemlock N42E 32.3' mrkd "C1/4 BT"  
 17" Maple N74E 18.7' do  
 20" Sugar S13E 24.7' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Sugar N20E 8.85' mrkd "1/16S BT"  
 4" Sugar S65E 7.45' do  
 6" Sugar S16W 17.9' do  
 7" Sugar N53W 6.05' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		●		33		34		35		36	
13													

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 01/12/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

