

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 32W T <u>48N</u> R <u>32W</u>	E13 <u>E1</u>
2. Property Controlling in Section	T _____ R _____ S _____ T _____ R _____ S _____ T _____ R _____	(Same Corner)
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10					2
5													
6		18		17		16				14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

T49N-R32W

I, Stephan J. Szyszkoski, in a field survey on 11/12/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 32-33 T49N-R32W and Sections 4-5 T48N-R32W. 1846 - Established by Austin Burt Deputy Surveyor midway and on the Township line between Section corners 80.00 chains east and west. 1978 - Corner remonumented and recorded by K.L.Sackett RLS who restored corner position at a found old rotted post in a pile of rocks the position of which "fits good with corners east and west and swamp edge south". Set 1"IDx24" I.pipe with 4" aluminum MDNR cap. 9" Spruce N18E 15.0', 9" Spruce S35E 19.7', 6" Spruce N42W 32.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original post and accessories were not recorded. Found the 1978 monument of record and did not accept it as marking the position for the corner. According to measurements made this date, the 1978 position is situated N39W 99.3' from the position monumented by the undersigned, being midway and on the Township line between Section corners 1 mile east and west, proportionate to the 1846 US survey. Measurements from the monumented proportionate position conform very well to the original record in 4 directions: North 5294.8'M (5287.9'R), South 5173.5'M (5171.1'R), East 5276.1'M (5280.0'R), West 5276.1'M (5280.0'R). The position also checks well with GLO record hill calls at 30.0 and 32.0 chains south. My measurements to other corners on Section 32 which were monumented or coordinated by Mr. Sackett show no evidence of measurement blunder on Sec. 32. But the 1978 position, does not, in fact, fit "good with corners east and west", is probably a perpetuation of an approximate position established by an unknown party, and is not accepted.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" Sugar N36E 4.2' mrkd "S33 NBT"
 17" Spruce S71E 31.25' "S4 NBT"
 5" Balsam S34E 19.8' "S4 NBT"
 11" Spruce S22W 42.8' "S5 NBT"
 Set sq'd cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/12/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities