

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 32W T <u>48N</u> R <u>32W</u> T _____ R _____	D13 <u>D1</u> (Same Corner)
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		3		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 11/12/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Section 32 T49N-R32W and Section 5 T48N-R32W. 1846 - Established by Austin Burt Deputy Surveyor midway and on the Township line between Section corners 40.00 chains east and west. Set Fir post. Fir 7" N42E 34 links, Fir 8" N7W 49 links. 1988 - Monumented by K.L.Sackett RLS midway between Section corners 1/2 mile east and west. Set Witness Corner on the N-S 1/4 line of Section 32 36.5' north of the corner position. Set 1"x32" I.pipe with 4" alum. MDNR cap. 8" Balsam S85W 19.8', 5" Balsam N02W 17.3', 7" Balsam N31E 14.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original corner and accessories were not recovered. The position for the corner now falls in the Sturgeon River. Did not accept the 1988 position for the corner. The 1988 position was determined using an erroneous 1978 position for corner E13 which was not accepted by the undersigned. The 1978 E13 position is N39W 99.3' from the E13 position used by the undersigned to reestablish D13 herein described. I reestablished the corner midway and on the Township line between monumented Section corners C13 and D13 2638.03' east and west, being proportionate to the original record. From the position thus established, the 1988 Witness Corner was found 74.5' north and 31.6' west. The Quarter corner position is not monumented. Set a Witness Corner on the N-S 1/4 line of Section 32 75.00' N00 deg. 34'18"E (true bearing) from the position for the Quarter corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx32" I.pipe with 4" alum. MDNR cap for a Witness Corner, 75.00' northerly of the Quarter corner position and on the N-S 1/4 line of Sec. 32 T49N-R32W. Set measuring nail with MDNR tag in the side of:
 9" Balsam West 51.4' 1988 scribing visible
 9" Balsam N60W 27.0' mrkd "WC BT"
 6" Balsam N16W 16.8' do
 4" Balsam N08E 25.95' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/12/2009
 Surveyor's Michigan License No. 33986