

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 32 T 49N R 32W	5
	S 32 T 49N R 32W	6
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 12/04/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 32) North 1/16 corner, Section 32. 1988 - monumented by K.L.Sackett midway and on line between North 1/4 corner and Center of Section. Set 1"IDx36" I.pipe with 4" aluminum MDNR cap. 4" Sugar N13W 28.1', 16" Cedar S62E 27.5', 4" Sugar S72W 19.8'.

(6-Sec. 32) Northeast 1/16 corner, Section 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 32) Found but did not accept the 1988 monument of record. The 1988 position was calculated and monumented in accordance with a position for the Center of Section 32 which was not correct and which has now been remonumented by the undersigned in the correct position. Established the corner midway and on a straight line between Quarter corner 1315.66' north and Center of Section (monumented Dec. 11, 2008) 1315.66' south. Removed the 1988 monument which was found N36W 11' distant.

(6-Sec. 32) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 22" Cedar S78E 19.6' mrkd "1/16S BT" 1988 BT
 9" Sugar N20W 39.1' old blazes do
 9" Sugar S47E 13.7' mrkd "1/16S BT"
 5" Sugar N63W 30.8' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" B.Ash N16E 4.3' mrkd "1/16S BT"
 5" B.Ash S30E 6.3' do
 15" Cedar S52W 8.6' do
 7" Cedar N22W 26.0' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/09/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities