

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 32W	F13
	T 48N R 32W	F1
	T _____ R _____	(same corner)
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

*T49N R32W*

I, Stephan J. Szyszkoski, in a field survey on 07/07/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(F13) Quarter corner common to Section 33 T49N-R32W and Section 4 T48N-R32W. 1846 - Established by W.A.Burt and Austin Burt, Deputy Surveyors, midway and on the Township line between Section corners 40.00 chains east and west. Set Fir post. Cedar 9 N67E 26 links, Cedar 16 N70W 16 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F13) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner on the curved Township line and at the position proportionate to the original record between Section corners 40.00 chains east (2638.04' M) and 120.00 chains west (13185.33' M).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F13) Set 1" IDx32" I.pipe with 4" alum. MDNR cap made firm in a mound of rock. Set measuring nail with MDNR tag in the side of:  
 11" Cedar S01W 19.35' mrkd "1/4S NBT"  
 4" Sugar N73W 15.35' do  
 4" Maple N37W 10.75' do  
 17" W.Pine N08E 26.5' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 07/09/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971