

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 32 T 49N R 32W _____	9
	S 32 T 49N R 32W _____	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_ 9 12/04/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(9-Sec. 32) East 1/16 corner, Section 32. 1988 - monumented by K.L.Sackett RLS midway and on a straight line between Quarter corner east and Center of Section west. Set 1"IDx36" I.pipe with 4" aluminum MDNR cap. 8" Sugar S83W 10.8', 4" Sugar N01W 11.2', 8" Sugar S74E 10.2'.

(8-Sec. 32) West 1/16 corner, Section 32. 1988 - monumented by K.L.Sackett RLS midway and on a straight line between Quarter corner C12 and Center of Section D12. Set 1"IDx36" I.pipe with 4" aluminum MDNR cap. 6" W.Pine S10W 22.9', 10" Sugar S45E 18.1', 10" Sugar N24E 21.6'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(9-Sec. 32) Found but did not accept the 1988 monument, the position of which was based on corners D12 and E12 which have been subsequently corrected. Established the corner midway and on a straight line between Center of Section D12 1303.92' west and Quarter corner E12 1303.92' east, both remonumented by the undersigned. Removed the 1988 monument, which was found N37W 37' distant.

(8-Sec. 32) Found but did not accept the 1988 monument of record. The 1988 position was calculated and monumented in accordance with a position for the Center of Section 32, D12, which was not correct and which has now been remonumented this date. Established the corner midway and on a straight line between C12 1304.21' west and said remonumented Center of Section D12 1304.21' east. Removed the 1988 monument which was found N34W 12.4' distant.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 15" Hemlock N78E 6.3' mrkd "1/16S BT"  
 6" Spruce S03E 22.6' do  
 18" Hemlock S45W 18.3' do  
 6" Hemlock N04W 5.0' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 11" Sugar N07E 30.3' old blazes 1988 BT  
 12" Sugar S55E 6.9' do do  
 8" W.Pine S45W 16.8' do do  
 14" W.Pine S25W 23.2' mrkd "1/16S BT"  
 Set sq'd Cedar post adjacent. Bearings are magnetic. The monument leans 0.2' to the west. The center of the cap marks the corner position.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 01/12/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities