

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 32W	B7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 09/11/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 18 and 19. 1852 - Established by Guy Carleton Deputy Surveyor on the Section line between Section corners 40.00 chains east and 35.19 chains west. Set post. Sugar 10" N23E 23 links, Sugar 10" S68E 10 links. 1854 - Abner Wood Examining Deputy Surveyor: West between Sections 18 & 19 ...40.09 Intersected 10 links North of post. Sugar 6" N22E 23 links, Sugar 9" S65E 9 links...77.21 Intersected West Boundary 40 links North of post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Found the distance between the NW and NE corners of Section 19 to be 77.438 chains, being 22.8 links longer than the 1854 record remeasurement. As observed elsewhere in this township, the Examining Surveyor's record seems more reliable than that of the original surveyor, and I therefore reestablish the corner proportionate to his measure and in accordance with his noted falling between the monumented Section corners S89 deg. 05' 04"E 2653.77' and N89 deg. 23' 34"W 2457.15' (Bearings Michigan Coordinate System of 1983, Zone 2111, grid).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 18" Y.Birch N59E 10.6' mrkd "1/4S NBT"
 6" Sugar S21E 18.7' do
 11" Sugar N85W 21.7' do
 8" Sugar N52W 26.8' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 12/09/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities