

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 49 NR 34W

Baraga

COUNTY

DESCRIPTION OF CORNER 1/4 cor. for secs: 18-19

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 5" J. Pine (1/4s NBT) N83°E 27 Lks.

5" J. Pine (1/4s NBT) S5°E 10 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established by proportionate measure and on line between two sec. cors. No evidence of original cor. Squared and scribed 4" J. Pine at cor. Cor. placed and wit. 5/14/59 with L. Stevens, D.F.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 8/10/59
REGISTERED LAND SURVEYOR