

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 34 W.

Paraga COUNTY

DESCRIPTION OF CORNER Meander Corner for Sections 28 & 29 on south shore of Big Lake.

DESCRIPTION OF CORNER MONUMENT 2" iron pipe with 3" brass cap.

WITNESSES TO CORNER 4-18-59

5" jack pine S 32°, E 21 links. Marked "MCBPT"

4" jack pine N 80°, W 6 links. Marked "MCBPT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. This corner was replaced as set by unknown surveyor. Found iron pipe with brass cap in proper position. Found Y. Pine bearing tree (Green) bearing S 42°, E 137 links. Tree in excellent condition. Scribe marks plain. Has been chopped out many years ago. Found by pacing from south while checking lines in area.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 4-29-59
REGISTERED LAND SURVEYOR