

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42... NR. 34 W. ...

... Laroga ... COUNTY

DESCRIPTION OF CORNER Section corner 17 - 18 - 19 - 20

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 7-22-58

8" jack pine N 24°, W 19 links. Marked "S1P13T"

8" jack pine S 45°, E 23 links. Marked "120WBT"

8" jack pine N 38°, S 45 links. Marked "1711T"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. Re-established corner by single proportionate measure on east and west center line of township according to method used to originally subdivide twp. Corner placed with L. Stevens, District Forester.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 5-1-52
REGISTERED LAND SURVEYOR