

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49.. NR. 34-35.. N

-----~~Alcona~~----- COUNTY

DESCRIPTION OF CORNER Section corner for sections 12, 15, 13, 24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 1" brass cap.

WITNESSES TO CORNER 7-22-58

9" jack pine S 46°, W 42 links. Marked "S24NSP"

9" jack pine S 58°, E 63 links. Marked "S12NSP"

8" jack pine N 45°, E 49 links. Marked "S12NSP"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. Re-established corner along twp. line to north and south by single proportionate measure. Found no evidence of original corner. Corner placed and witnessed with L. Stevens, District Forester.

SURVEYORS SEAL

Billy D. Buckler

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 5-1-59