

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 34-35 W

Baraga COUNTY

DESCRIPTION OF CORNER Section corner for sections 30, 31, 35, 36

DESCRIPTION OF CORNER MONUMENT 1" pipe with brass cap

WITNESSES TO CORNER 7-22-58

8" jack pine N 76°, 10 links. Marked "825 67"

9" jack pine S 42°, 5 links. Marked "830 67"

7" jack pine S 20°, 3 links. Marked "831 67"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Re-established corner by single proportionate measure along north and south
two line. Using corners 3 miles north and 2 miles south. Found no evidence of original
corner. Corner placed and witnessed with L. Stevens, District Forester.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 5-1-59
REGISTERED LAND SURVEYOR