

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR 34 W.

Baraga COUNTY

DESCRIPTION OF CORNER Section corner 3, 4, 9, 10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 2-13-58

5" jack pine N 54° E 54 1/2 links. Marked "14113"

4" jack pine N 12° E 22 1/2 links. Marked "83151"

4" jack pine S 8° E 29 links. Marked "81011"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. Re-established corner on N-S line by single proportionate measure,
being corners 1 mile north and 1 mile south. No evidence of original corner.
Corner placed with L. Stevens, District Forester.

SURVEYORS SEAL

Billy D. Suckler
SIGNED Billy D. Suckler DATE 5-1-59
REGISTERED LAND SURVEYOR