



MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49... NR. 34 W...

Baraga COUNTY

DESCRIPTION OF CORNER ... section corner 2 - 3 - 10 - 11 ...

DESCRIPTION OF CORNER MONUMENT ... 1" pipe with 4" brass cap ...

WITNESSES TO CORNER ... 7-13-58 ...

... 3" jack pine N 77°, W 77 links. Marked "S370F" ...

... 2" jack pine S 3°, W 37 links. Marked "S101BF" ...

... 3" jack pine N 65°, W 23 links. Marked "S241F" ...

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Re-established corner by single proportionate measure between corners 1
- mile north and 1 mile south. Found no evidence of original corner. Corner placed with
L. Stevens, District Forester.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 5-1-58
REGISTERED LAND SURVEYOR