

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 34

Baraga

COUNTY

DESCRIPTION OF CORNER Section corner 16 - 17 - 20 - 21

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 7-22-58

6" jack pine S 70°, W 111 links. marked "S20N1P"

6" jack pine S 32°, E 71 links. marked "S21N1P"

6" jack pine N 46°, E 23 links. marked "E10N1P"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Re-established corner by single proportionate measure on east and west center line of township according to method used to originally subdivide twp. Found no evidence of corner. Corner placed and witnessed with L. Stevens, District Forester.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 5-1-59
REGISTERED LAND SURVEYOR