

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

*BARRAGA*

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 49 N. R. 34 W.	I 9 & J 9
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner I 9: Wood Post (Possibly found)
- Tamarack 10 N61W 24 (Not Found)
- Tamarack 5 S21E 62 " "

Found 3 posts or points of post in place; oldest (possibly original) was a 2"x2"x4' squared tamarack post, with point in swamp bottom and upper part preserved under moss. Next oldest was a squared picket, also rotted off. Youngest, and found standing was a squared tamarack post found S2°E 3½ lks. from first point.

Corner J 9: Original post or its accessories not found. No subsequent monuments found.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner I 9: The first two found posts are obviously very old, and it is possible that the oldest is the original. This post probably was not even seen by the party who set the last post. The point lies 80.073 ch. E'ly of an original sec. corner, and nearly on line with the 1/4 corner (also probably original) between the two sec. corners. Therefore, accepted the oldest post as probably being original, and on 9/15/71, replaced it with a new monument.

Corner J 9: Re-established 6/8/73 on line between section corners 40.01 ch. to E and to W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Witnesses for Corner I 9:**
- Tamarack 7 N35°W (mag.) 35.6 ft. "S22, NBT"
  - Tamarack 6 N81°E (mag.) 29.4 ft. "S23, NBT"
  - Tamarack 5 S24°W (mag.) 52.1 ft. "S27, NBT"
- Witnesses for Corner J 9:**
- Tamarack 6 N 3°E (mag.) 8.3 ft. "1/4S, NBT"
  - Tamarack 11 S64°E (mag.) 19.8 ft. "1/4S, NBT"

Also squared and scribed a 6" tamarack N26°E (mag.) 3.5 ft. from corner.

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE July 6, 1973  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581