

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 49 N. 34 E. S. _____	I 9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 15 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Wood post (possibly found)  
 Tamarack 10 N61W 24 (not found)  
 Tamarack 5 S21E 62 " "

Found three posts or points of posts in place. Oldest was a 2"x2"x4' squared tamarack post, point in swamp bottom with upper part lying preserved under the moss. Next oldest was 1½"x1½"x6½' squared picket, also rotted off. Youngest, and found standing, was a 3"x3"x5' squared tamarack post found S2°E 3½ links from first post.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

The first two found posts are obviously very old, and it is very possible that the oldest is the original. This post probably was not even seen by the party who set the last post. The point lies 80.073 ch. E'ly of an original section corner, and nearly on line with the 1/4 cor. (also probably original) between the two section corners. Therefore, accepted the oldest post as probably being original, and perpetuated it as such.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1" I. D. x 36" iron pipe with 4" aluminum cap.

Tamarack 7 N35°W (mag.) 35.6 ft. "S22, NBT"  
 Tamarack 6 N81°E (mag.) 29.4 ft. "S23, NBT"  
 Tamarack 5 S24°W (mag.) 52.1 ft. "S27, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 22, 1973  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581