

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 49 N. R. 34 E. W.	K 7
2. PROPERTY CONTROLLING IN SECTION 14 _____	T. 49 N. R. 34 E. W.	13, 14, & 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K 7:** No evidence of original post or its accessories. Found a 1" I.D. x 24" iron pipe in place, probably set by Ford Motor Co. personnel, and re-witnessed by D. DeLaMater, R.L.S. on 5/18/50.
- Corners 13 & 14:** Not established in original survey, and only by approximation, subsequently.
- Corner 16:** Not established in original survey. Established previously by Ford Forestry Center personnel and marked with a 4"x4" scribed wood post.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K 7:** Corner perpetuated as found on 10/20/71, as it appears consistent with other known original corners in vicinity.
- Corner 13:** Established 5/15/72 at intersection of quarter-quarter section lines.
- Corner 14:** Established 11/9/71 on line between Sec. Cor. 19.940 ch. S and 1/4 cor. 19.940 ch. N.
- Corner 16:** Established 11/9/71 on line between Sec. Cor. 19.874 ch. E and 1/4 cor. 19.874 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for all four corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Witnesses for Corner K7:** (DeLaMater) W. Birch 7 N 8°E (mag.) 48.8 ft. "S13, NBT"
(Enger) J. Pine 7 S66°E (mag.) 128.5 ft. "S24, NBT"
- Witnesses for Corner 13:** J. Pine 6 S26°W (mag.) 5.4 ft. "1/16S, BT"
J. Pine 5 N67°W (mag.) 9.4 ft. "1/16S, BT"
- Witnesses for Corner 14:** J. Pine 14 S75°W (mag.) 47.7 ft. "1/16S, BT"
J. Pine 8 N57°E (mag.) 71.7 ft. "1/16S, BT"
- Witnesses for Corner 16:** J. Pine 7 N57°W (mag.) 29.7 ft. "1/16S, BT"
J. Pine 6 N21½°E (mag.) 26.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 22, 1973

MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581